

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


Company- OKMAR OIL CO.
Farm- Joseph

No. 1

SEC. 11 T. 11 R. 17W
SW SW SW

Total Depth. 3909'
Comm. 2-17-58 Comp. 3-3-58
Shot or Treated.
Contractor. Murfin Drlg. Co.
Issued. 4-19-58

County Ellis
KANSAS



Elevation. 1995 KB

Production. SWDW

CASING:

8 5/8" 230' w/170 sx cem.
5 1/2" 3613' w/600 sx cem.

Figures Indicate Bottom of Formations.

sand, clay	55
shale	229
shale, shells	460
sand, shale	535
shale, shells	625
sand	815
red bed, shells	1172
Anhydrite	1215
shale, shells	1560
salt, shale	1750
shale, shells	1790
shale, lime, shells	1900
lime, shale	3115
lime	3205
lime, shale	3290
lime	3516
Conglomerate	3548
lime "Arbuckle"	3906
Quartzite	3909
Total Depth	

TOPS:

Anhydrite	1172
Topeks	2953
Heebner	3223
Toronto	3244
Lansing, Kansas City	3271
Conglomerate	3516
Arbuckle	3548

DST #1 3255-90 Rec. 60' gas.
68' oil gas cut mud. 'F 180,
FF 185, BHP 1160#.

DST #2 3290-3302 Rec. 250' salt
wtr. IF 130#, FF 280#, BHP 1100#.

DST #3 3322-56 Rec. 150' muddy
salt wtr. IF 180#, FF 240#, BHP
1180#.

DST #4 3441-52 Rec. 10' mud.
No Pressures.