


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- OKMAR OIL CO.
Farm- Christine No. 3

SEC. 15 T. 14 R. 17W
SE NE NE

Total Depth. 3547'
Comm. 9-21-58 Comp. 10-1-58
Shot or Treated.
Contractor. Murfin Drlg. Co.
Issued. 12-20-58

County Ellis KANSAS



CASING:
8 5/8" 177' cem w/150 sx.
5 1/2" 3551' cem w/150 sx.

Elevation. 2004' KB

Production. 55 BOPD

Figures Indicate Bottom of Formations.

surface hole	176
shale-shells	450
sand-shale	525
shale-shells	630
sand	820
redbed-shale-shells	1040
redbed-shale	1175
Anhydrite	1217
shale-shells	1560
salt-shells	1750
shale-shells	1860
lime-shale	2280
lime	2365
lime & shale	2700
shale-lime shells	2960
shale-lime	3295
lime	3465
lime-shale	3522
Conglomerate	3545
Arbuckle	3547
Total Depth	

TOPS:

Anhydrite	1175
Heebner	3230
Toronto	3250
Lansing-Kansas City	3279
Conglomerate	3522
Arbuckle	3545

DST #1 3262-3295