


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
503 East Murdock, Wichita, Kansas

Company- LEBEN DRILLING CO.
Farm- Dinkel No. 2

SEC. 16 T. 14 R. 17W
NW SE NW

Total Depth. 3543
Comm. 7-19-55 Comp. 7-30-55
Shot or Treated.
Contractor. Leben Drilling Co.
Issued. 11-12-55

County Ellis
KANSAS



CASING:

8 5/8 @ 1175'
5 1/2 @ 3543'

Elevation. 1995 RB

Production. 25 BOPD

Figures indicate Bottom of Formations.

clay, shale & sand	190
shale & shells	630
sand	820
shale & shells	1168
anhydrite	1206
red bed, shale & shells	1405
salt, shale & shells	1840
shale & shells	1900
lime & shale	2020
shale & shells	2050
broken lime	2160
lime	2345
broken lime	2485
lime & shale	2750
broken lime	2830
shale & shells	2960
lime & shale	3010
lime	3150
lime & shale	3214
shale	3217
lime & shale	3230
lime	3455
lime & shale	3503
Arbuckle	3543
Total Depth	

SCOUT TOPS:

Anhydrite	1170
Heebner	3214
Lansing	3260
Arbuckle	3503