


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company. ANSCHUTZ DRILLING COMPANY
Farm. Jacob Stecklein No. 1

SEC. 17 T. 14 R. 17W
NE NE SW

Total Depth. 3558
Comm. 10-2-56 Comp. 10-12-56
Shot or Treated.
Contractor.
Issued. 11-24-56

County Ellis
KANSAS



CASING:
8 5/8" 206' cem w/150 sx.
5 1/2" 3556' cem w/100 sx.

Elevation. 1982 R.B.

Production. Dry

Figures Indicate Bottom of Formations.

soil, cand	40
shale, shells	215
shale	390
shale, sand	480
shale, shells	620
sand red, shale	820
shale, red bed	1080
red bed	1160
anhydrite	1165
shale	1270
salt	1290
shale, shells	1810
lime	1995
lime, shale	3228
lime	3357
lime, shale	3516
conglomerate, Arbuckle	3537
Arbuckle	3558
Total Depth	

Tops:	Sample	Electric Log.
Heebner	3212	3213
Toronto	3231	3232
Lansing	3257	3260
Base Kansas City	3481	3484
Conglomerate	3496	3497
Arbuckle	3530	3533
Total Depth	3558	3557

Drill Stem Tests:

- #1 3257-3287, Open 1 hr, weak blow 20 mins & died. Recovered 90' of oil-specked mud. IBHP 1150# (20 mins.) IFF 0#, FFP 80#, FBHP 920#.
- #2 3530-3537, Open 1 hr. Weak steady blow for 10 mins., weak intermittent blow for 50 minutes. Rec. 33' of oil cut mud., IFF 0#, FFP 0#, BHP 630#, (20 mins.) (Still building).
- #3 3535-3544, Open 1 hr. Weak blow throughout. Rec. 65' of heavily oil cut mud. IFF 0#, FFP 0#, BHP 880# (30min.)
- #4 3544-3558 Open 1 hr. Weak steady blow throughout. Rec. 190' very heavily oil-cut mud, 60' of froggy, muddy oil. IFF 0#, FFP 100#, BHP 910#.