


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company T. O. LILYSTRAND JR.
Farm Ruder No. 1

SEC. 25 T. 14 R. 17W
SW NE NW

Total Depth. 3515
Comm. 4-25-55 Comp. 5-4-55
Shot or Treated.
Contractor. Stickle Drlg. Co.
Issued. 6-18-55

County Ells KANSAS



Elevation. 1953 KB

Production. dry

CASING:

8 5/8" 255' cem. w/200 sx

Figures Indicate Bottom of Formations.

clay, sand, shale & shells	257
shale & shells	515
Dakota sand	730
redbed & shale	970
shale & shells	1050
lime & shale	1150
redbed, shale & shells	1300
salt, shale & shells	1675
lime & shale	1865
shale & shells	2000
lime & shale	2145
shale w/lime strks	2160
lime & shale	2300
shale & shells	2385
shale & lime	3305
lime	3409
lime & Conglomerate	3459
Conglomerate	3484
lime	3515
Total depth	

Tops:		Electric Log Tops
Hebner	3163	3160
Toronto	3182	3178
Lansing	3211	3209
Conglomerate	3439	3436
Arbuckle	3476	3473
		3513 RTD

Drill Stem Test #1
Packer set at 3479. Total depth 3484'.
Tool open 20 minutes. Weak blow for 2
minutes. Recovered 8' mud. BHP 0 1/2 in
15 minutes.