

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

60230

Company - BRIDGEPORT OIL CO., INC.
Farm - Stecklein "A" No. 1.

SEC. 13
SE NE

T. 14

R. 18 W

Total Depth. 3594' PB 3584'
Comm. 6-30-44 Comp. 7-28-44
Shot or Treated.
Contractor.
Issued. 8-12-44 Rotary O-3579
Cable 3579-94

County. Ellis
KANSAS



CASING:
8 5/8" 1176' Cem.
5 1/2" 3569' Cem.

Elevation. _____

Production. Dry

Figures Indicate Bottom of Formations.

cellar	10	
clay	65	
sand	95	
shale	200	After plugging back, well
shale & sand rock	430	tested 1/3 to 1/2 BWPH.
sand	445	Shot w/Lane-Wells 22 shots
shale & sand rock	540	3583-3571.
shale & shells	600	Swbbd and bailed hole dry.
sand	830	Hole making approx. 1-1/3
shale	950	BWPH and show free oil
red bed	1020	AT w/500 gals.
red bed & shale	1130	
red bed	1175	After AT swbbd hole dry and
anhydrite	1230	swbbd 10 Bbls. WPH w/very
red rock & sand	1400	light show oil.
shale, red rock & salt	1555	
salt & shells	1825	
shale & shells	1882	
lime & shale	2270	
lime	2310	
sandy lime	2360	
shale & shells	2440	
lime & shale brks	2479	
lime & shale	2565	
2565=2595		
shale & lime shells	2595-2695	
shale & shells	2810	
lime	2825	
lime & shale	2870	
shale & lime	2969	
lime & shale	3144	
lime	3164	
lime & shale	3250	
red rock & lime	3273	
lime & shale	3276	
lime	3331	
lime brkn	3388	
lime	3430	
lime & shale	3470	
lime	3538	
shale & chert	3548	
chert & lime	3555	
lime	3579	
3579=3582		
reddish dol., wht chert, grn		
& gy shale	3582- 3585	
buff dense dol., green shale,		
wht chert	3590	
buff sdy dolomite	3593	
water sand, 750' wtr in 12		
hrs w/sli. sh oil	3594 Total Depth.	
P. B.	3584	

Tops: DF
Anhydrite 1175
Heebner 3250
Toronto 3274
Base Oread 3282
Lansing 3290
Conglomerate 3541
Arbuckle 3557

3541
1282
-1559

3582
1601

3590
1982
1608