

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
Wichita, Kansas


Company - HANLON-BOYLE, INC.  
Farm - Emery No. 1

SEC. 23 T. 14 R. 18W  
SW SW NE

Total Depth. 3677  
Comm. 7-15-48 Comp. 7-31-48  
Shot or Treated.  
Contractor. Glenn Peel Drlg. Co., Inc.  
Issued. 12-3-49

County. Ellis

KANSAS



Elevation. \_\_\_\_\_

Production. Dry

CASING:

8" set @ 237'

Figures Indicate Bottom of Formations.

Clay & sand	195
Shale & shells	280
Sand	320
Shale, shells & sd.strks	475
Sand	580
Sd. strks. & shale	640
Sand	815
Shale, shells & sd. strks	870
Shale	978
Shale & shells	1120
Iron & shale	1185
Shale & pyrite strks.	1190
Anhydrite	1218
Shale & shells	1250
Red shale & shells	1405
Shale & sand strks.	1490
Shale	1500
Shale & sand	1625
Shale	1665
Shale, shells & sd.strk	1810
Broken lime & shale	1890
Lime & shale	1984
Brkn. ls. & str. shale	2100
Lime & shale	2270
Shale & shells	2355
Shale & brkn. ls.	2470
Lime & shale	2530
Shale & lime	2998
Lime	3595
Lime & shale	3627
Arbuckle lime	3633
Arb. ls. & br. chert	3677

Total Depth

FORMATION TOPS:

Anhydrite	1183
Topeka ls.	2973
Heebner sh.	3236
Lans.-K.C.	3285
B. L-K.C.	3510
Congl.	3545
Arbuckle	3572