


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- MALLONEE DRLG. CO., INC.
Farm- RUPP No. 1

SEC. 32 T. 14 R. 18W
NE NE SE

Total Depth. 3671'
Comm. 12-20-56 Comp. 1-10-57
Shot or Treated.
Contractor. Mallonee Drlg. Co., Inc.
Issued. 3-23-57

County Ellis
KANSAS



Elevation. 2051' KB

Production. 50 BOPD

CASING:

8 5/8" 368' w/135 sx cem.
5 1/2" 3669' w/125 sx cem.

Figures indicate Bottom of Formations.

surface soil-post rock	
	50
shale-shells	155
sdv shale	200
shale-shells	580
sand-shale	650
sand	885
shale-shells	1125
shale-red bed	1220
Anhydrite	1265
shale-shells	1670
salt-shale	1875
shale-shells	1915
lime-shale	2255
lime	2325
shale-shells	2525
shale-lime	2630
shale-shells	2740
lime-shale	2960
lime	3603
Conglomerate	3671
Total Depth	

TOPS:

Anhydrite(scout)	1220
Heebner	3280
Toronto	3300
Lansing	3327
Kansas City	3552
(B/Kansas City)	3552
Conglomerate	3617

DST #1 3370-3582 Open 1 hr.,
SI 20 min., gas to surface in
37 min., rec. 1500' oil, IF 400#,
BHP 1100#.

DST #2 3401-3409 Open 1 hr.,
SI 20 min., strong blow 20
min. decreasing thruout remainder
of test. Rec. 370' salt wtr.
BHP 720#.

DST #3 3499-3515 Open 1 hr.
SI 20 min., rec. 550' gas,
110' oil & GC muddy salt wtr.
BHP 1100#.