

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock,
Wichita, Kansas


Company- JOSEPH JR AND ORVILLE FURTHMYER
Farm- Furthmyer (Fee) No. 1

SEC. 5 T. 14 R. 19W
NW SW NW

Total Depth. 3891
Comm. 10-10-53 Comp. 10-20-53
Shot or Treated.
Contractor. Strain Drlg. Co.
Issued. 4-9-55

County Ellis

KANSAS



CASING:
8 5/8" 183' cem. w/125 sx
5 1/2" 3890' cem. w/125 sx

Elevation. 2276 R.B. Est.

Production. 113 BO / 10% wtr

Figures indicate Bottom of Formations.

All Measurements rotary bushing

post rock	70
blue shale	183
shale & shells	450
sand & shale	600
shale & shells	910
hard sand	915
shale & sand	1250
redbed & shale	1545
shale	1549
Anhydrite	1590
shale & shells	2130
lime & shale	3435
lime	3805
lime & shale	3865
Conglomerate	3887
Arbuckle	3891
Total depth	

Tops:	
Anhydrite	1549
Topeka	3270
Heebner	3511
Toronto	3532
Lansing-KC	3555
Base Kansas City	3804
Conglomerate	3847
Arbuckle	3887

DST by Sun Cementing Co.
3735-3745, Tool open 30 minutes.
Recovered 5' of drilling mud. BHP 625#.
15 Min. (Weak blow for 6 minutes)
No electric logs run