


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- STANOLIND OIL & GAS COMPANY
Farm- Gay E. Riedel "C" No. 1

SEC. 6 T. 14 R. 19W
NE NW NE

Total Depth. 3912
Comm. 1-30-53 Comp. 2-23-53
Shot or Treated.
Contractor.
Issued. 4-4-53

County Ellis
KANSAS



CASING:
8 5/8" 170' cem. w/125 sx
5 1/2" 3908' cem. w/1000 sx

Elevation. 2287 RDB.

Production. 1030 BO

Figures Indicate Bottom of Formations.

clay	25
sand	35
clay	50
shale & sand	170
shale	400
shale & shells	670
red bed	725
shale	1095
sand	1250
shells & shale	1515
anhydrite	1608
shale & shells	1775
shale	2100
shale & lime	2375
lime	2540
shale	2555
lime	2690
lime & shale	2860
lime	2900
shale & lime	3145
lime	3374
congl.	3908
lime, chert	3912
Total Depth	

Tops:
Lansing 3567
Arbuckle 3907

DST: #1 3595-3605' tool
open 1/2 hr. rec. 445' SW
x 30' GCM BHP 1270#.
DST: #2 3737-51' tool
open 1/2 hr. rec. 70' oil
cut mud. BHP 270#.
DST: #3 3902-11' tool
open 1/2 hr. rec. 25 BO
120' mud cut oil. BHP 1075#.

Acidize: 500 gal. Max. pressure
250# broke to 150# took acid.
in 39 mins. 4 hr. swab test
2000' off bottom 16.28 BOPH
4 hr. swab test 2500' off
bottom 10.00 BOPH.

Perm. Bench Mark
7' above 2" outlet in
8-5/8" Bradenhead.