


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- DAVIS BROTHERS & TRANSIT CORP.
Farm- Riedel "A" No. 1

SEC. 8 T. 14 R. 19W
C E/2 NE SW

Total Depth. 3841'
Comm. 1-23-58 Comp. 2-3-58
Shot or Treated.
Contractor. Transit Corp.
Issued. 6-28-58

County Ellis
KANSAS



CASING:
8 5/8" 190' cem w/125 sx.
5 1/2" 3827' cem w/200 sx.

Elevation. 2209' KB

Production. 86 BOPD

Figures Indicate Bottom of Formations.

shale & shells	950
sand	1190
shale	1215
shale & shells	1475
anhydrite	1502
shale	1505
shale & shells	2085
shale & lime str.	2305
lime & shale	2583
shale	2715
shale & lime str.	3086
lime & shale	3140
shale & lime str.	3265
lime & shale str.	3544
lime	3750
lime & shale	3794
lime	3828
lime	3841
Total Depth	

TOPS:	
Anhydrite	1485
Heebner	3458
Toronto	3483
Lansing	3504
Base Kansas City	3747
Marmaton Chert	3786
Conglomerate	3799
Sand, Conglomerate Zone	3815
Sand Conglomerate	3828
Arbuckle	3841

Ran Electric log.

DST #1 3694-3750', op 1 hr, fair to strong blow. Rec. 750' gas, 80' VHOCM, 84' oil, ISIP 1250#, FSIP 1100#, FP 0# - 0#.