


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
 503 East Murdock, Wichita, Kansas

Company- FRONTIER OIL CO.
 Farm- Von Feldt No. 5

SEC. 9 T. 14 R. 19W
 SW SW SW

Total Depth. 3810'
 Comm. 3-19-58 Comp. 3-31-58
 Shot or Treated.
 Contractor. Red Tiger Drlg. Co.
 Issued. 8-9-58

County Ellis
 KANSAS



Elevation. 2207' DF

Production. 132 BOPD

CASING:

8 5/8" 214' cem w/135 sx.
 5 1/2" 380' cem w/150 sx.

Figures Indicate Bottom of Formations.

post rock & soil	75
blue shale & shells	214
shale & shells	945
sand	1160
shale & shells	1480
Anhydrite	1525
shale & shells	2120
lime & shale	2340
shale & shells	2400
lime & shale	2570
shale & lime shells	2610
shale & lime	3500
lime	3810 RTD
Total Depth	

TOPS:

Anhydrite (Drillers)	1480
Heebner	3455
Toronto	3480
Lansing-Kansas City	3501
Base Kansas City	3743
Arbuckle	3802