

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


Company- FRED B. ANSCHUTZ
Farm- Wiesner No. 1

SEC. 14 T. 14 R19W
SW SW SE

Total Depth. 3851
Comm. 5-16-55 Comp. 5-26-55
Shot or Treated.
Contractor. Anschutz Drilling Co., Inc.
Issued. 7-2-55

County Ellis

KANSAS



Elevation. 2150 DF

Production. Dry

CASING:

8 5/8 261' w/ 150 sx cmt.

Figures indicate Bottom of Formations

shale	900
sand	1125
shale & shells	1250
red bed, shale & shells	1428
anhydrite	1470
shale & shells	2120
lime	2178
shale	2208
lime & shale	2405
lime	2480
lime & shale	3563
lime	3631
lime & shale	3812
Arbuckle	3851
Total Depth	

TOPS:	E. LOG	SAMPLE
Heebner	3432	3432
Lansing	3480	3481
Conglomerate	3772	3775
Arbuckle	3811	3811

DST #1: 3591-3631, open 30 min. SI
15 min. rec. 10' mud, BHP 0#

DST #2: 3641-66, open 30 min. SI 15
min. straddle test, 184' tail pipe,
rec. 4' mud, BHP 1070#