

PRYOR & LOCKHART, INC.
Kraus No. 1.

SEC.17 T.14 R.19 W
NE SE SW

DISCOVERY WELL

Total Depth. 3806'
Comm. 9-2-42 Comp. 9-19-42
Shot or Treated.
Contractor. Sharon Drlg. Co., Inc.
Issued. 12-12-42

County. Ellis



CASING:

10" 100' Cem.
5 1/2" 3799' Cem.

Elevation.

Production.

Minimum Well

Figures Indicate Bottom of Formations.

cellar	10
sand	30
clay	45
shale	470
sand	615
sand & shale	746
shale	888
sand & shale	1137
shale	1465
shale & red bed	1640
shale	1970
shale & shells	2100
shale	2115
lime	2135
shale	2150
lime	2160
lime & shale	2485
lime	2640
red rock	2652
sand	2666
lime	2830
shale & shells	3005
shale	3050
shale & shells	3095
shale & lime	3127
shale & shells	3180
lime	3195
shale	3220
lime	3608
lime & chert	3638
lime	3768
lime & chert	3795
conglomerate	3798
conglomerate sand	3806
Total Depth.	

Tops:	
Ft. Riley	2320
Lansing	3498
Conglomerate	3795
Conglomerate Sand	3798