


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
 508 East Murdock, Wichita, Kansas

Company- SHIELDS OIL PRODUCERS
 Farm- Perry No. 2

SEC. 27 T. 14 R. 19W
 NE SW SE

Total Depth. 3811'
 Comm. 10-1-57 Comp. 10-12-57
 Shot or Treated.
 Contractor. Shields Drlg. Co.
 Issued. 1-4-58

County Ellis
 KANSAS



Elevation. 2000' RB

Production, Phy. Pot. 39 BOPD

CASING:

8 5/8" 280' w/150 sx cem.
 5 1/2" 3810' w/150 sx cem.

Figures indicate Bottom of Formations.

surface clay-shale-shells	
	280
clay shale-red bed-	
sand	1036
sand	1140
red bed	1462
Anhydrite	1503
shale-shells	2050
shale-lime stkr	2200
shale w/lime	2500
lime-shale	2572
lime	2655
lime-shale	2959
shale w/lime stks	3099
lime-shale	3232
lime	3799
lime-sand	3811 RTD
Total Depth	

TOPS:

Heebner	3442
Toronto	3461
Lansing-Kansas City	3484
Marmaton chert	3759
Conglomerate	3778
Gorham sand	3783
Arbuckle	3809

DST #1 3518-3560 Open 1 hr.
 w/weak blow thruout. Rec. 70'
 watery mud. BHP - 1120#/20 min.

DST #2 3653-3692 Open 1 hr.
 w/good steady blow thruout. Rec.
 835' gas, 15' OCM, 75' muddy oil,
 75' froggy oil. BHP - 1120"/20
 min.