


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- SHIELDS OIL PRODUCERS
Farm- Perry No. 3

SEC. 21 T. 14 R. 19W
SW SE SE

Total Depth. 3857'
Comm. 8-25-59 Comp. 9-4-59
Shot or Treated.
Contractor. Shields Drlg. Co.
Issued. 11-7-59

County Ellis
KANSAS



CASING:
8 5/8" 281' cem w/175 ex.

Elevation. 2217' RB

Production. Dry

Figures Indicate Bottom of Formations.

shale & shells	525
shale, shells & sand	1400
red bed	1477
Anhydrite	1520
shale	2100
shale & lime	2840
lime	2960
shale & lime	3243
lime	3857 RTD
Total Depth	

TOPS:

Anhydrite (scout)	1477
Heebner	3469
Toronto	3483
Lansing-Kansas City	3506
Marmaton	3782
Conglomerate	3798
Conglomerate Sand	3804
Arbuckle	3848

DST #1 3572-3627', op 1 hr. w/strong blow thruout, rec. 600' gas cut salt water. BHP 1160#/20 mins.,

DST #2 3642-3680', op 1 hr, w/strong blow thruout, rec. 540' salt water, BHP 725#/20 mins.

DST #3 3690-3715', op 1 hr., w/weak blow for 25 mins., rec. 10' rotary mud, BHP 0#.

DST #4 3850-3857', op 1 hr., w/fair blow thruout, rec. 65' SOC salt water. 200' salt water. BHP 1100#/20 mins.