


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- TENNESSEE GAS TRANSMISSION
Farm- Kraus No. 1

SEC. 21 T. 14 R. 19W
SE SE NW

Total Depth. 3777'
Comm. 10-5-56 Comp. 11-9-56
Shot or Treated.
Contractor. Shelley-Miller Drlg. Co.
Issued. 12-1-56

County Ellis
KANSAS



CASING:

Elevation. 2147'

8 5/8" 264' w/150 sx cem.
5 1/2" 3775' w/100 sx cem.

Production. 97 BOPD & 7 BW

Figures indicate Bottom of Formations.

Meas. fr top RB
shale-shells 1000
sand 1090
red bed 1417
Anhydrite 1453
red bed 1710
lime-shale 2390
lime 2465
lime-shale 2600
lime 2710
lime-shale 3265
lime 3777
Total Depth

TOPS:

Heebner 3400
Tercinto (scout) 3419
Lansing 3444
B/Kansas City 3692
Conglomerate 3750
Arbuckle 3774

DST #1 - 3453-3520 Open 1 hr.,
SI 20"-rec. 465' muddy salt
wtr. BHP 1075 - IF 125, FF 400.

DST #2 - 3748-73 - Open 1 hr.,
10' SOCM - 165# BHP.

DST #3 - 3747-77 - 80' gas,
400' HOCM- BHP, 1030-FP 1030.
DP - to RTD 3777-swab 18 hrs.
36 B O-no wtr. 250 acid. Swab
36.26 BO/2 hrs. 500' OB-Swab
27 BO/7 hrs.