


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- FRONTIER OIL COMPANY
Farm- Feitz No. 1

SEC. 28 T. 14 R. 19W
NW NE NE

Total Depth. 3833'
Comm. 6-17-59 Comp. 6-29-59
Shot or Treated.
Contractor. Red Tiger Drlg.
Issued. 9-26-59

County Ellis
KANSAS



CASING:

8 5/8" 200' cem w/135 sx.
5 1/2" 3808' cem w/150 sx.

Elevation. 2210' DF

Production. 80 BOPD

Figures indicate Bottom of Formations.

cellar	10
clay post rock	40
shale shells	200
shale & shells	620
sand	710
shale & sand	735
shale	750
sand	950
shale & red bed	1477
Anhydrite	1517
shale shells	1650
shale & shells	2045
shale & lime	2100
lime & shale	2330
lime shale	2520
lime & shale	2680
shale & lime	2820
lime shale	3010
lime & shale	3450
lime	3730
lime & shale	3797
chert & shale	3826
Arbuckle	3833 RTD
Total Depth	

TOPS:	
Anhydrite	1475
Heebner	3455
Lansing-Kansas City	3501
Base Kansas City	3743
Marmaton Chert	3782
Conglomerate	3794
Arbuckle	3826