

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
503 East Murdock, Wichita, Kansas

Company. PEEL-HARDMAN PRODUCERS
Farm. Schwaller No. 1

SEC. 36 T. 14 R. 19W
SW SW SW

Total Depth. 3704
Comm. 4-11-51 Comp. 5-6-51
Shot or Treated.
Contractor. Peel-Hardman
Issued. 6-7-52

County Ellis
KANSAS



8 5/8" 160' cem.
5 1/2" 3692' cem.

Elevation. 2099

Production. Pmp. 50 BO & 35% w.

Figures Indicate Bottom of Formations.

sand & clay	24
shale	45
shale & shells	165
shale	750
sand	925
shale	1155
shale & red bed	1315
anhydrite	1355
shale	1485
shale & shells	2140
lime & shale	3000
shale & shells	3130
lime & shale	3440
lime	3693 RTD
lime	3704
Total Depth	

Scout Tops:
Arbuckle 3689

Moved in cable tools 5-1-51,
drilled cement and drilled
deeper to 3697 1/2', small
show of fine oil; acidized
with 500 gals. 5-3-51; drilled
deeper to 3704', bailed; acidized
with 750 gals. on 5-4-51; swab
tested; run tubing and rods and
completed well 5-6-51