

KANSAS GEOLOGICAL SOCIETY
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
 KANSAS GEOLOGICAL SOCIETY BUILDING
 508 EAST MURDOCK - WICHITA, KANSAS

COMPANY **V. P. DE WEESE, SR**

SEC. 5 T. 14 N. 2W
 LOC. C SE SE

FARM **De Bold**

NO. **1**

COUNTY **Saline**

TOTAL DEPTH **3156**

COMM. **6-17-66**


COMP. **6-23-66**

SHOT OR TREATED

CONTRACTOR **Blackstone Drlg.**

ISSUED **10-1-66**

KANSAS



CASING

20	10		
15	8 5/8"	@ 200'	w/125 SX.
12	6		
13"	@ 95'	8 4 1/2"	@ 3153' w/60 SX.

ELEVATION **1212' KB**

PRODUCTION **PMP 25 BOPD,**

TR Wtr. (Maq Dolo 3153-56)

FIGURES INDICATE BOTTOM OF FORMATIONS

0	to	85	Surface Sand		
85	to	140	Shale	TOPS: SAMPLE	
140	to	200	Lime & Shale		
200	to	560	Lime	Mississippi	2605
560	to	1490	Shale & Lime	Kinderhook	2796
1490	to	1740	Lime	Maquoeta Shale	3064
1740	to	2000	Shale & Lime	" Dolomite	3153
2000	to	2503	Lime		
2503	to	2625	Shale & Lime		
2625	to	2772	Mississippi		
2772	to	2960	Lime & Shale		
2960	to	3064	Lime		
3064	to	3153	Shale		
3153	to	3156	Maquoeta		
		3156	T. D.		

Cut 12 1/4 in. hole and reamed a 17 1/2 in hole to 95 ft. and run 13 in. pipe. Cut 12 1/4 in. hole and run 200 ft. of 8 5/8 in. surface casing and cemented on bottom with 125 sacks cement and 3 1/2 Calcium Chloride. Plug down at 7:00 P.M., June 17, 1966. Cut 7 7/8 in. hole to 3156 ft. and run 3153 ft. of 4 1/2 in. O.D. casing and cemented 8ft. off bottom at 3153 ft. with 60 sacks cement. Plug down at 1:45 A.M., June 23, 1966.

TOPS: Mississippi - 2605' B/Mississippi - 2771' Hunton - 2953'
 Maquoeta Shale - 3064' Maquoeta Dolomite - 3153'

Measurements taken from K. B.

CERTIFICATE

I, **H. J. Plouffe**, President of Blackstone Drilling, Inc. do hereby certify that the above and foregoing is a true and correct copy of log on your DeBold #1 located on the C-SE/4 SE/4 of Sec. 5-14-2W, Saline County, Kansas as reflected by the files of Blackstone Drilling, Inc.

H. J. Plouffe
 H. J. Plouffe, President

Subscribed and sworn to before me a Notary Public in and for McPherson County, Kansas this 24th day of June, 1966.