

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- **KREBBS & ELLIS**
 Farm- **Balaum**

No. **2**

SEC. **30** T. **14** R. **2W**
 CS/2 SE SW

Total Depth. **3225**

Comm. **10-11-63**


Comp. **10-20-63**

Shot or Treated.

Contractor. **White & Ellis**

Issued. **5-23-66**

County **Saline**
KANSAS



CASING:

8 5/8" Q 204' w/150 sx.

4 1/2" Q 3219' w/50 sx.

Elevation. **1234' KB**

Production. **FMP 25 BOPD & 50% Wtr.**
(MAQ 3219-25)

Figures Indicate Bottom of Formations.

cellar	5
soil & sand	50
sand & shale	100
lime & shale	175
lime	203
Anhydrite	235
shale & lime	350
shale & lime stks. & red rock	1185
limed shale	1300
shale & lime stks.	1470
shale & sandy stks.	1510
lime & shale	1670
lime	1820
shale & lime	1960
lime	2060
shale	2130
lime & shale stks.	2315
lime & shale	2657
lime	2921
shale	3101
lime	3142
shale	3217
dolomite & chert	3225
Total Depth	

TOPS: LOG

Kansas City	1960
Mississippi	2657

SAMPLE TOPS:

Conglomerate	2657
Mississippi	2666
Kinderhook Sand	2921
Hunton	3035
Maquoketa Shale	3142
Maquoketa Dolomite	3219