


WELL LOG BUREAU -- KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - L. B. JACKSON COMPANY ET AL
Farm - Norton No. 1

SEC. 32 T. 14 R. 2W
SWE NE

Total Depth. 3296'
Comm. 6-19-47 Comp. 6-29-47
Shot or Treated. Acid. w/1000 gals.
Contractor.
Issued. 11-14-47

County. Saline
KANSAS



Elevation. 1314 *set by*

Production. Pot. 347 BO

CASING:

10-3/4" 240' Cem. w/175 sx
5-1/2" 3286' Cem. w/100 sx

Figures Indicate Bottom of Formations.

shale & sholls	190
shale ~ lime	450
lime, shale & sand	655
lime & shale	765
shale w lime shells	1055
shale & sand	1375
shale	1575
lime	1655
lime brkn & shale	1740
lime	1775
shale & lime	2055
lime	2210
shale & lime	2620
shale	2695
lime	2805
shale w lime	2860
shale, lime & chert	2900
lime	2935
shale	3100
shale & lime	3275
Cored	3296
shale green	3285
lime showing oil	3296
Total Depth	

2670
1314

1356

Tops:

K. C. Lansing	2042
Miss.	2670 -1356
Kinderhook shales & limes	2936
Hunton lime	3070
Sylvan Shale	3205
Viola Lime (Sylvan Mar)	3285