


WELL LOG BUREAU — KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - L. B. JACKSON DRILLING CO.
Farm - Cravens No. 1

SEC. 20 T. 14 R. 2W
NW SE SW

Total Depth. 3452'
Comm. 6-4-47 Comp. 7-23-47
Shot or Treated.
Contractor.
Issued. 8-23-47

County. Saline
KANSAS



CASING:
10 3/4" 240'
5 1/2" 3275' P

Elevation. 1307 act 1940.

Production. Dry

Figures Indicate Bottom of Formations.

shale, shells & gravel 10-160
shale & shells 240
lime 330
lime & shale 470
lime 580
lime & shale 1050
shale 1070
lime 1080
lime & shale 1140
shale & lime streak 1315
lime hrd 1365
lime & shale 1385
shale & shells 1470
shale 1580
lime & shale 1740
shale 1840
lime 1845
lime hrd 1935
lime & shale 2005
shale 2010
lime 2145
sand 2160
lime 2185
lime & shale 2253
lime 2275
sand 2295
shale & lime 2340
lime 2475
lime & shale 2510
lime 2590
shale 2655
lime 2985
shale 3055
shale & lime 3095
lime 3100
sand & lime streak 3140
lime 3170
shale 3225
shale & lime 3260
cored-shale & lime 3278

Tops:
K. C. Lime 2060
Miss. Lime 2685
Kinderhook X 2025 ?
Hunton 3095
Sylvan Shale 3200
Viola 3276
Viola White 3340
Simpson 3395

Show oil 3275-3278

lime 3310
lime hrd 3325
lime brwn 3340
lime wh 3401
lime brwn 3410
shale green 3424
shale sdy 3445
sand wtr 3451
sand wtr 3452
Total Depth

Abandoned as a dry hole.