


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY  
 508 East Murdock, Wichita, Kansas

Company- PHILLIPS & SANDERSON  
 Farm- Helen Baulan No. 1

SEC. 30 T. 14 R. 2W  
 SE NE SW

Total Depth. 3225  
 Comm. 9-13-50 Comp. 9-25-50  
 Shot or Treated.  
 Contractor. E. K. Carey  
 Issued. 12-12-53

County Saline  
 KANSAS



CASING:

8 5/8" 200' cem. w/200 sx, circ.  
 5 1/2" 3219' cem. w/ 50 sx

Elevation. 1233 DF

Production. Swb. 54 BO / 234 wtr.

Figures indicate Bottom of Formations. K.B.

rotary table, base & cellar	8
clay	18
sand	50
sand & gravel	95
shale & shells	150
lime	280
lime & shale	415
lime	416
lime & shale	1385
shale	1510
lime & shale	1560
lime	1670
shale & redrock	1692
shale & lime	1725
lime	1785
shale	1815
lime	1840
lime & shale	2050
lime	2285
shale & lime	2715
lime	2870
lime & shale	2895
lime	2934
shale & lime	3058
lime	3140
lime & shale	3219
lime	3225
Total depth	

Geologist Tops: K.B.	
Miss. lime	2655
Kinderhook	2932
Hunton	3044
Maquoketa shale	3139
Maquoketa dolomite	3219
Pay 3219-25	
Rotary Total depth	3225