

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock,
Wichita, Kansas


21-14-20W

Company- SHIELDS OIL PRODUCERS, INC.
Farm- Catholic Church No. 1

SEC. 21 T. 14 R. 20W
SE SE SE

Total Depth. 3823'
Comm. 9-5-61 Comp. 9-14-61
Shot or Treated.
Contractor. Shields Drlg. Co.
Issued. 11-18-61

County Ellis KANSAS



CASING:
8 5/8" 309' cem w/225 sx.

Elevation. 2170' RB

Production. Dry

Figures Indicate Bottom of Formations.

surface soil, clay & shale	310
shale & shells	430
shale, sand, redbed	1180
shale & redbed	1432
Anhydrite	1470
redbed, shale, shells	1615
shale & shells	2040
shale	2130
lime	2230
lime & shale	2430
lime	2530
lime & shale	3280
lime	3745
lime & chert	3780
chert & sand	3807
lime & sand	3823 RTD
Total Depth	

TOPS:

Anhydrite (scout)	1432
Heebner	3409
Lansing-Kansas City	3449
Marmaton	3750
Conglomerate Sand	3798
Arbuckle	3808
Reagan	3816

DST #1 3786-3806', op 1 hr, w/weak blow
dying in 5 min. Rec. 10' rotary mud.
IFP 0#, FFP 0#, FBHP 480#/20 mins.