


Company - SUNRAY OIL CORP.
 Farm - Dreiling "B" No. 1.

SEC. 2 T. 14 R. 20 W
 S W SE NW

Total Depth. 3872'
 Comm. 10-9-44 Comp. 11-1-44
 Shot or Treated.
 Contractor. R.W. Rine Drlg. Co.
 Issued. 12-9-44

County. Ellis
 KANSAS



CASING:

8 5/8" 1540' Cem.
 5 1/2" 3849' Cem.

Elevation. _____

Production. Pot. 450 B.

Figures Indicate Bottom of Formations.

sand & shale	0-155
shale	310
shale & shells	690
sand	705
shale	845
shale & sand	940
shale	1020
sand	1245
shale	1535
anhydrite	1580
shale	2185
lime & shale	2225
lime	2665
shale & lime	2980
lime	3050
lime & shale	3290
lime	3870
lime & sand	3872
show oil	3845
Total Depth	

Tops:

Howard	3179
Topeka	3221
Heebner	3442
Lansing	3470
Winterset	3616
Base KC	3713
Marmaton Cht.	3786
Ch. Congl	3837
Arbuckle	3858