


Company - SUNRAY OIL CORP.
Farm - Orth No. 1.

SEC. 2 T. 14 R. 20 W
NEc SW

DISCOVERY WELL

County. Ellis
KANSAS

Total Depth. 3852½'
Comm. 7-30-44 Comp. 8-22-44
Shot or Treated.
Contractor.
Issued. 10-21-44



CASING:
8 5/8" 1539'
5 1/2" 3835' Cem.

Elevation. 2242

Production. Phy.Pot.563 B.

Figures Indicate Bottom of Formations.

post rock	480
shale	540
sand & shale	860
sand	885
shale	945
shale & sand	1100
red bed, shells	1500
red rock	1513
red bed	1535
anhydrite	1575
red bed	1625
shale & red rock	1910
sand & shale	1965
shale & shells	2115
lime	2140
shale	2160
shale & shells	2400
shale blue	2440
shale & shells	2550
lime	2585
shale & shells	2615
lime	2645
shale & shells	2665
lime	2760
shale & shells	2850
lime	2885
shale & shells	2935
lime	2975
shale & shells	3235
lime	3260
shale & shells	3273
lime	3405
shale	3415
lime	3800
lime cherty	3825
lime	3852½'
Total Depth	

Tops:

Anhydrite	1535
Topeka	3235
Heebner	3470
K.C.	3537
Congl	3803
Simpson	3830 3
Arbuckle	3833
Reagan sand	3846 13