


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - WHITE EAGLE OIL CO.
Farm - Dinkle No. 1

SEC. 3 T. 14 R. 20W
SE NE SE

Total Depth. 3932
Comm. 6-1-49 Comp. 6-19-49
Shot or Treated.
Contractor.
Issued. 7-16-49

County. Ellis
KANSAS



CASING:
8 5/8" 1284' cem w/700 sx.

Elevation. _____

Production. Dry

Figures Indicate Bottom of Formations.

surface clay, calchi	
	40
shells, sand, shale	540
shale, lime	800
shale, lime shells,	
pyrite	915
shale, shells, sand	1240
shale	1280
anhydrite	1284
shale, sand, limeshells	
	1635
lime, shale	2165
lime, shale	2280
lime	2325
lime, shale	2400
shale	2500
lime sdy	2545
lime, shale	3595
lime	3648
lime, shale	3668
lime	3834
shale, sand	3844
lime	3932
Total Depth	

Tops:	
Heebner	3478
Dedds lime	3500
Lansing K. C.	3548
Conglomerate	3816
Arbuckle	3848
Reagan	3882

Hole full heavy drilling mud.
Bottom plug set at 225' cem w/20
sc cement by Halliburton. Second
plug at 25' cem w/10 sx. cement,
surface capped.