


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- SKILES OIL CORPORATION
Farm- Befort No. 1

SEC. 11 T. 14 R. 20W
CN/2 NW SE

Total Depth. 3856
Comm. 10-31-51 Comp. 11-17-51
Shot or Treated.
Contractor.
Issued. 2-23-52

County Ellis
KANSAS



Elevation. 2205 D.F.

Production. pot. 138 bbls oil

CASING:

10" 170' cem w/150 sx
5 1/2" 3855' cem w/125 sx

Figures Indicate Bottom of Formations.

sand, shale, shells	376
shale	1500
anhydrite	1545
shale	2082
sand hard	2169
sand, shale	2380
sand hard	2480
lime	2535
lime, shale	3335
lime	3488
shale, lime	3536
lime	3825
lime, sand	3850
sand	3856
Total Depth	

Tops:	
Heebner	3460
Brown Lime	3488
Lansing	3501
Conglomerate	3772
Gorham	3816

Perforated with 24 shots -
3845-51; 500 gal. acid; swabbed
6 bopk; potential 138 bbls.