

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas


Company- SHIELDS OIL PRODUCERS  
Farm- Solomon "B" No. 1

SEC. 22 T. 14 R. 20W  
SE SW NW

Total Depth. 3886'  
Comm. 12-8-56 Comp. 12-21-56  
Shot or Treated.  
Contractor. Shields Drilling Co., Inc.  
Issued. 1-19-57

County Ellis

KANSAS



Elevation. 2234' RB

Production. Dry

Figures indicate Bottom of Formations.

surface clay	25
sand	35
shale, lime & shells	270
shale & shells	450
sand & shale	1190
shale & red bed	1470
red bed	1499
Anhydrite	1533
red bed & shale	1735
shale	1825
shale, shells & salt	2135
shale & shells	2270
shale & lime	2500
lime	2560
lime & shale	2655
shale & lime streaks	2755
lime & shale	2955
shale & lime streaks	3060
shale & lime	3235
lime	3690
lime & shale	3729
lime	3812
lime, chert & shale	3850
lime & Conglomerate	3863
Conglomerate, lime & sand	3885
Conglomerate	3886 RTD
Total Depth	

TOPS	
Heebner	3476
Toronto	3498
Lansing/Kansas City	3515
Marmaton Chert.	3813
Conglomerate sand	3860
Reagan Sand	3877
Quartzite	3885

DRILL STEM TEST  
DST #1 3879'-86', tool op.  
30 min. w/strong blow thru-out,  
rec. 510' muddy salt wtr.  
BHP 1150#/15 min.