

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


14-14-20W

Company- THUNDERBIRD DRILLING, INC.
Farm- Cerney No. 1

SEC. 14 T. 14 R. 20W
NE NW NW

Total Depth. 3840'
Comm. 12-18-56 Comp. 1-3-57
Shot or Treated.
Contractor. Thunderbird Drilling Company
Issued. 1-26-57

County Ellis KANSAS



Elevation. 2149' DF

CASING:
8 5/8" @298' w/150 sx cem.

Production. Dry

Figures Indicate Bottom of Formations.

surface clay	
& shale, rock	163
shale	560
sand	910
shale & sand	1110
sand	1175
shale & shells	1450
Anhydrite	1490
shale & shells	1806
shale & lime	2990
lime	3000
shale & lime	3265
lime	3705
shale & lime	3760
Cherty lime	3780
shale & lime	3800
shale & sand	3805
sand	3840 RTD
Total Depth	

SCOUT TOPS	
Anhydrite	1450
Heebner	3400
Toronto	3422
Lansing	3440
Base/Kansas	
City	3686
Marmaton lime	3735
Conglomerate	
Shale	3766
Reagan Sand	3792
Pre-Cambrian	3837