



Cont'd

Company - Rine Drlg. Co.  
Farm - Madden No. 1  
17-11-21W  
NW NW NE

No show 3252-3274

No show 3316-3329

No show 3340-3349

No show 3363-3376

No show 3376-3395

No show 3425-3438

No show 3468-3475

No show 3493-3498

No show 3564-3574

No show 3597-3608

Trace spotted brown stain  
3617-3629

No show 3632-3643

Trace dead black stain

DST: water 3643-3648

No show 3656-3662

No show 3702-3708

Trace dead oil 3716-18

Possible trace dead stain  
3752-3765

No show 3790-3818

some show free oil 3909-3924

chert section from 3909-56

may be Marmaton or possibly

Mississippian in place.

Looks like Chattanooga

3956-3964

Trace free oil 3971-3978

Top Arbuckle 3998; no show

in Arbuckle

DST: #1 3640-52; open 1

hr. rec. 205' salt wtr, no

oil or gas bottom hole pressure

1205#.

DST: #2 3897-3939; open 1 hr.

rec. 120' oil cut mud; no

water bottom hole pressure 740#.

DST: #3 3948-90; open 1 hr.

rec. 825' salt wtr bottom

hole pressure 1167#.

DST: #4 4005-50; open 30 mins.

rec. 30' mud, no oil, gas or

wtr bottom hole pressure 990#.

Perforated 17 holes 3971-77;

got 100' water Set plug @ 3960'

Perforated 72 holes 3909-39;

slight show oil

Acidized with 500 gals. bailed

4 to 5 gals. acid water and a

cupful of oil per hr.

Hydrofractured through perforation

3909-39'

Swabbed down--lacked 80 bbls. of

rec. oil land

Tested. Swabbed for 12 hrs. rec.

12 bbls. oil and 11 bbls. kerosene

and acid wtr.

Swabbed for 6 hrs. rec. 1 1/2 bbls. oil

and 6 1/2 bbls. formation wtr

Perforated 3800-11 with 24 holes;

hole full of water.

All measurements are from the top

of the rotary bushing which is

three feet above the derrick floor.

