

WELL LOG BUREAU-- KANSAS GEOLOGICAL SOCIETY
Wichita, Kansas

Company. STANOLIND OIL & GAS CO.
Farm. Ernest Jesse No. 1

SEC. 32 T. 14 R. 24W
C NE NE

Total Depth. 4515

Comm. 9-28-49

Comp. 10-22-49

County. Trego

KANSAS

Shot or Treated.

Contractor.

Issued. 11-12-49



CASING:
13" set @ 238'

Elevation. _____

Production. Dry

Figures Indicate Bottom of Formations.

Sand	20
Shale	65
Sand & shale	225
Shale & shells	284
Shale	390
Shale, shale & sand	530
Sand & shale	670
Sand, shale & iron	800
Shale & shells	1055
Red bed, shale & shells	1170
Sand	1395
Red bed, shale & shells	1665
Anhydrite	1695
Shale & shells	2480
Lime	2545
Lime & shale	2605
Lime	2740
Lime & shale	3335
Lime	3420
Lime	3820
Lime & shale	3955
Lime	3985
Lime & shale	4045
Lime	4100
Lime & chert	4130
Ch. Conglomerate	4141
Chert, lime & shale	4185
Lime	4295
Lime	4365
Lime	4475
Lime & chert	4515

Total Depth

FORMATION TOPS:

Anhydrite	1647
Heebner	3369
Lansing	3403
Marmaton	3884
Mississippi	4022
Viola	4266
Arbuckle	4339

DST 4029-41, op. 1 hr. rec. 25' mud
& 10' oil BHP zero, gr.37.9
DST 4129-41, op. 2 hrs. closed 15 min.
rec. 100' wtr cut mud
w/specks oil BHP 1020
DST 4339-65, op. 1 hr. rec. 240' wtr.
BHP. 1040

Ran Schlumberger 3200-4515