

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY

502 East Murdock,

Wichita, Kansas

13-14-28W


Company- AURORA GASOLINE CO. & SKILES OIL CORP.
 Farm- Hefner No. 1

SEC. 13 T. 14 R. 28W
 NE NE NE

Total Depth. 4479
 Comm. 5-31-52 Comp. 7-5-52
 Shot or Treated.
 Contractor.
 Issued. 7-26-52

County Gove

KANSAS



CASING:

10 3/4" 160 cem. w/100 sx.

Elevation. 2531 D.F.

Production. Dry

Figures indicate Bottom of Formations.

shale & shells	2431
shale & limo	2975
lime & shale	3877
lime	4132
lime & shale	4292
lime	4479 RTD
Total Depth	

Tops: K.B.	
Heebner shale	3697
Lansing-K.C.	3734
Marmaton	4038
Spargen	4318
Warsaw	4379

D.S.T. 3958-65, open 37 mins. 7 min.

weak blow, shut in 15 min., rec. 8'

drlg. mud, BHP 695 #.

3958-65 white-lgt buff fine med. grain

lime fair intergranular por. good showing

of free oil, slight odor.

D.S.T. # 2 (straddle packer)

3969-96, open 1 hr. 1 hr. strong blow, shut

in 15 min., rec. 423' salt wtr. BHP 940 #.

initial flow press. 40 #. 3976-80 wh fine

grain xlyn. lime, spotted stain & sat.

3988-92 wh med grain xlyn. lime, spotted

stain & sat.

Marmaton (top 4038)

No shows or traces were found in this form.

Miss. (top 4318)

No shows or oil traces were found in this form.