

IMPORTANT
Kans. Geo. Survey request
samples on this well.

15-063-20388

KANSAS DRILLERS LOG

S. 8 T. 14 R. 30 E
W

API No. 15 — 063 — 20,388
County Number

Loc. NW SW

County Gove

Operator
Chief Drilling Co., Inc.

Address
905 Century Plaza Wichita, Kansas 67202


Well No. #1 Lease Name Swart

Footage Location
feet from (N) (S) line feet from (E) (W) line

Principal Contractor Geologist
Warrior Drilling, Inc. Tom Wesselowski

Spud Date Total Depth P.B.T.D.
October 9, 1978 4555'

Date Completed Oil Purchaser
October 19, 1978 None



Locate well correctly
Elev.: Gr. 2780

DF 2782 KB 2785

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
	12 1/4"	8 5/8"	28 lb.	265'	Common	165	2% gel

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

TUBING RECORD

Size	Setting depth	Packer set at

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated

INITIAL PRODUCTION

Date of first production		Producing method (flowing, pumping, gas lift, etc.)			
RATE OF PRODUCTION PER 24 HOURS	Oil bbls.	Gas MCF	Water bbls.	Gas-oil ratio	CFPB
Disposition of gas (vented, used on lease or sold)			Producing interval(s)		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator Chief Drilling Co., Inc. DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:

Well No. #1 Lease Name Swart Dry Hole

S 8 T 14SR 30W^E_W

WELL LOG
 Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries. SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
DST #1 3898-3944' 30-30 60-30 Wk. stdy. bl. Rec. 400' SW IBHP: 1244# FBHP: 1220# FP: 55-255#			Anhydrite	2232
			Base Anhy.	2284
			Heebner	3839
			Lansing	3878
			BKC	4190
			Marmaton	4214
DST #2 4022-4100' 30-30 60-30 Wk. stdy. bl. Rec. 150' MW IBHP: 1170# FBHP: 1095# FP: 55-153#			Ft. Scott	4370
			B/Cher. Lime	4472
			Top Miss.	4496
			LTD	4554
			RTD	4555
DST #3 4111-90' 30-30 30-30 Wk. bl. 30" Rec. 25' OSpkd.M IBHP: 1133# FBHP: 1110# FP: 47-65#				

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received _____
 Signature Bill G. Lahar
 Title Bill G. Lahar, Geologist
 Date October 25, 1978