

API No. 15 — 063 — 20,231
 County Number

Operator
Donald C. Slawson

Address 408 One Twenty Bldg. Wichita, Kansas 67202

Well No. #1 Lease Name Jilg "A"


Footage Location
 feet from (N) (S) line feet from (E) (W) line

Principal Contractor Slawson Drilling Company Geologist Ralph Ruwwe-R.B. Jenkins

Spud Date October 15, 1974 Total Depth 4105' P.B.T.D.

Date Completed October 23, 1974 Oil Purchaser N/A

S. 1 T. 14 R. 30W ^E/_W
 Loc. 150' S of C SE NE
 County Gove



Elev.: Gr. 2719
 DF 2724 KB 2727

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4"	8 5/8"		252'	60/40 Poz	175 sx	

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

TUBING RECORD		
Size	Setting depth	Packer set at

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated

INITIAL PRODUCTION

Date of first production		Producing method (flowing, pumping, gas lift, etc.)			
RATE OF PRODUCTION PER 24 HOURS		Oil	Gas	Water	Gas-oil ratio
		bbls.	MCF	bbls.	CFPB
Disposition of gas (vented, used on lease or sold)				Producing interval (s)	

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator Donald C. Slawson

DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:
Dry Hole

Well No. #1

Lease Name Jilg "A"

s 1 T 14 S R 30 W^E_W

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.


FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
			EL Tops	
Surface Hole	0	260	ANHY	2154 (+573)
Shale and Shells	260	1020	HEEB	3736 (-1009)
Shale and Sand	1020	1771	TORO	3758 (-1031)
Shale and Shells	1771	2045	LANS	3776 (-1049)
Shale and Lime	2045	2154	STARK	4010 (-1283)
Anhydrite	2154	2187	B/KC	4079 (-1352)
Shale	2187	2590	LTD	4105 (-1378)
Lime and Shale	2590	3780		
Lime	3780	3895		
Lime and Shale	3895	3970		
Lime	3970	4105		
RTD	4105			

DST #1 3841-3864, 30"-45"-45"-60"
Weak Blow Increasing to Fair,
Rec. 160' Muddy Water w/few spots oil.
ISIP 1037#, IFP 26-62#, FSIP 983#,
FFP 62-107#

DST #2 4005-4050, 30"-45"-30"-45"
Weak Blow 30", very weak intermittent
Blow 30", Rec. 45' Mud w/spots heavy oil.
ISIP 930#, IFP 31-35#, FSIP 814#, FFP 35-47#.

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received



James C. Remsburg
Signature

James C. Remsburg, Petroleum Engineer

Title

November 1, 1974

Date

ANY:

Donald C. Slawson
408 120 Building
Wichita, Kansas 67202

1-14S-30W

LEASE:

Jilg "A" #1
C SE NE Sec. 1-14S-30W
Gove County, Kansas

TOTAL DEPTH:

4105 feet

CONTRACTOR:

Slawson Drilling Company, Inc.

COMMENCED:

October 15, 1974

COMPLETED:

October 23, 1974

CASING:

Set 8 5/8" @252' w/175 sx

0-260	Surface Hole
260-1020	Shale and Shells
1020-1771	Shale and Sand
1771-2045	Shale and Shells
2045-2154	Shale and Lime
2154-2187	Anhydrite
2187-2590	Shale
2590-3780	Lime and Shale
3780-3895	Lime
3895-3970	Lime and Shale
3970-4105	Lime
4105	RTD

STATE OF KANSAS)

) SS.

COUNTY OF SEDGWICK)



I, JAMES C. REMSBERG, of the Slawson Drilling Company, Inc. upon oath state that the above and foregoing is a true copy of the log of the Jilg "A" #1 well.

James C. Remsberg

 JAMES C. REMSBERG

Subscribed and sworn to before me this 1st day of November, 1974

Dolores B. Coady

 Dolores B. Coady, Notary Public

My Commission Expires:

DOLORES B. COADY
 STATE NOTARY PUBLIC
 SEDGWICK COUNTY, KANSAS
 Comm. Expires Mar. 7, 1975