


640 Acres  
N



Locate well correctly

API # 15-063-20,150

1-14-30W

Lease Name: Jilg "A" Well No. 1  
 Well Located: C NW NE  
Gove SEC 1 TWP 14S RGE 30W  
 Operator: Pickrell Drilling Company  
 Address: 705 Fourth National Bank Bldg., Wichita, Kansas  
 Elevation: Ground 2740 D.F. 2742 K.B. 2745  
 Type Well: (Oil, gas, dry hole) Dry Hole

Drilling Commenced: 11/3/ 1972 Drilling Completed: 11/27 1972  
 Well Completed: 19 Total Depth 4390'  
 Initial Production: \_\_\_\_\_

Casing Record

Size: 8-5/8" Set at 252' Size: \_\_\_\_\_ Set at \_\_\_\_\_  
 Size: \_\_\_\_\_ Set at \_\_\_\_\_ Size: \_\_\_\_\_ Set at \_\_\_\_\_

Liner Record

Size: \_\_\_\_\_ Set from \_\_\_\_\_ To \_\_\_\_\_

Cementing

<u>Casing Size</u>	<u>Sacks</u>	<u>Type Cement and Additives</u>
<u>8-5/8"</u>	<u>140</u>	<u>3/2 Cement</u>
_____	_____	_____
_____	_____	_____

Perforations

<u>Formation</u>	<u>Perforated Interval and Number Shots</u>
_____	_____
_____	_____
_____	_____

Electric Log Run (Show type log and depths covered)

GR-N, Guard-Cal. (Great Guns)

(Fill in formation and related information on reverse side)

1-14-30w  
Jilg A-1

FORMATION, TESTING AND COMPLETION RECORD

Show Drill Stem Tests,  
Well Stimulation and  
Production Tests

Formation	Top	Bottom
Surface, Soil, Clay	0	140.
Shale	140	1800
Shale - Shale	1800	2173
Hydrite	2173	2218
Shale	2218	2555
Shale	2555	2860
Shale	2860	3060
Shale & shale	3060	3690
Shale	3690	3750
Shale & Shale	3750	3785
Shale	3785	3995
Shale, RTD	3995	4390

DST # 1 3792-3802: Open 2 hrs., strong blow, rec. 120' gas in pipe, 1080' total fluid, 30' clean oil, 1050' salt water. IBHP 920#/30", FBHP 899#/60", IFP 31#, FFP 480#.

DST # 2 3810-3830: Open 40 mins. very weak blow 28 min Rec. 65' muddy water, scum oil. IBHP 1098#/30", FBHP 1087#/45", IFP 10#, FFP 31#.

DST # 3 3930-3992: Open 40 mins., weak blow 13 mins. Rec. 5' mud, no show. IBHP 42#/30", FBHP 31#/45", IFP 21#, FFP 21#.

DST # 4 3984-4021: Open 2 hrs, strong blow thruout. Rec. 1056#/30", FBHP 1025#/60", IFP 63#, FFP 470#.

C.F.S.

3805  
3883  
3880  
3921  
3995  
4024  
4230  
4360  
4390

ELECTRIC LOG TOPS

Anhy 2168  
top 3532  
Heeb 3752  
Tor 3774  
Lans 3790  
KC 3948  
Stark 4019  
BKC 4090  
Maem 4115  
Pawn 4200  
Myrick Sta 4240  
Ft Sc 4264  
Cher 4292  
Johnson Zn 4340  
Cong 4355  
Osage 4363  
Gil. More City 4382  
LTD RTD 4395

Slope Tests

2000  
2500  
3000  
3500  
4000