

SIDE ONE

AFFIDAVIT OF COMPLETION FORM

State Geological Survey
WICHITA, BRANCH (REV) AGO-1

36-19-30W

This form shall be filed in duplicate with the Kansas Corporation Commission, 200 Colorado Derby Building, Wichita, Kansas 67202, within ten days after the completion of the well, regardless of how the well was completed.

Attach separate letter of request if the information is to be held confidential. If confidential, only file one copy. Information on side one will be of public record and side two will then be held confidential.

Circle one: Oil, Gas, Dry, SWD, OWVO, Injection. Type and complete **ALL** sections. Applications must be filed for dual completion, commingling, SWD and injection.

Attach wireline logs (i.e. electrical log, sonic log, gamma ray neutron log, etc.).
KCC # (316) 263-3238. (Rules 82-2-105 & 82-2-125)

OPERATOR Beren CorporationAPI NO. 15-063-20,545ADDRESS 970 Fourth Financial CenterCOUNTY GoveWichita, Kansas 67202

FIELD _____

**CONTACT PERSON Evan MayhewPROD. FORMATION PawneePHONE (316) 265-3311LEASE Coberly "B"PURCHASER Central Crude CorporationWELL NO. 1ADDRESS 402 Commerce PlazaWELL LOCATION SW NE NEWichita, Kansas 67202DRILLING Warrior Drilling, Inc.

_____ Ft. from _____ Line and

CONTRACTOR

_____ Ft. from _____ Line of


ADDRESS 905 Century Plazathe SEC. 36 TWP. 14S RGE. 30WWichita, Kansas 67202

WELL PLAT

PLUGGING _____

CONTRACTOR _____

ADDRESS _____

KCC
KGS ☒
(Office Use)TOTAL DEPTH 4362 PBTD 4329SPUD DATE 12-4-81 DATE COMPLETED 3/11/82ELEV: GR 2651 DF _____ KB 2656DRILLED WITH (ROTARY) TOOLSAmount of surface pipe set and cemented 8-5/8" @ 135' DV Tool Used? _____

A F F I D A V I T

STATE OF KANSAS, COUNTY OF SEDGWICK SS, I, _____DON W. BEAUCHAMP OF LAWFUL AGE, BEING FIRST DULY SWORN UPON HIS OATH,DEPOSES THAT HE IS GEOLOGIST (FOR)(OF) BEREN CORPORATIONOPERATOR OF THE COBERLY "B" LEASE, AND IS DULY AUTHORIZED TO MAKETHIS AFFIDAVIT FOR AND ON THE BEHALF OF SAID OPERATOR, THAT WELL NO. 1 ONSAID LEASE HAS BEEN COMPLETED AS OF THE 11th DAY OF MARCH, 19 82, AND THAT

ALL INFORMATION ENTERED HEREIN WITH RESPECT TO SAID WELL IS TRUE AND CORRECT.

RECEIVED
STATE CORPORATION
MAR 31 1982

SIDE TWO

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

36-14-30w
SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Surface Clay	0	446		
Sand and clay	446	1570		
Sand and shale	1570	2060		
Anhydrite	2060	2094		
Shale	2094	2920		
Shale and lime	2920	3543		
Lime	3543	3752		
Shale	3752	3805		
Shale and lime	3805	3900		
Lime	3900	4362		
RTD	4362			

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used				Depth interval treated	
1550 gallons 15% HCl				4153-83	
Date of first production		Producing method (flowing, pumping, gas lift, etc.)		Gravity	
3/11/82		Pumping			
RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio	CFP
	90 bbls.	0 MCF	2 % 2 bbls.	-----	
Disposition of gas (vented, used on lease or sold)			Perforations 4153-57, 4179-83		

Report of all strings set — surface, intermediate, production, etc. CASING RECORD (New) or ☐

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12½"	8-5/8"	20#	315	60-40 pozmix	200	2% gel, 3% CC
Production	7-7/8"	5½"	14#	4386	60-40 pozmix	250	10% salt, 10# gel, 3/4% CFR-2
			TOP STAGE		Lite	350	
					Common	50	

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
TUBING RECORD			2	DPJS	4179-83
Size	Setting depth	Pecker set at	2	DPJS	4153-57
2-3/8	4318	-----			

36-14-30W

WELL LOG

December 29, 1981

Coberly "B" #1
SW NE NE SEC. 36-14-3
Gove County, Kansas

OPERATOR: Beren Corporation
CONTRACTOR: Warrior Drilling Inc.
COMMENCED: 12-4-81
COMPLETED: 12-15-81

8 5/8" @ 135' w/200 sx.

0	446	Surface Clay
446	1570	Sand & Clay
1570	2060	Sand & Shale
2060	2094	Anhydrite
2094	2920	Shale
2920	3543	Shale & Lime
3543	3752	Lime
3752	3805	Shale
3805	3900	Shale & Lime
3900	4362	Lime

4 1/2" @ 4361 w/200 sx/


We certify that the above and foregoing is a true and correct copy of
the log on the #1 Coberly B located in Gove County, Kansas.

RECEIVED
STATE CORPORATION COMMISSION
JAN 11 1982
CONSERVATION DIVISION
Wichita, Kansas

Warrior Drilling, Inc.


F. W. Shelton, Jr., Vice President

Subscribed and sworn to before me this _____ day of _____, 1981.



Martha E. Gustin Notary Public