

State Kansas County Russell

Company Messman-Rinehart Oil Co. Well No. 1

Farm Ida Mahoney


Survey Geol. @ Hollywood Motel, Russell, Ks.

Block No. 358 Sec. 30 Twp. 14 S Range 12 W

Co-Ord. 3135 Elev. 1713' K/B

NW/4 NW/4 NW/4

1712' D/F
1709' Gr



M-R Rig

- 25% - A. A. Seeligson, Jr.
- 25% - L. J. Plym
- 25% - Chicago Group (Anderson, McDermott, McNeill)
- 25% - M-R Oil Co.

ORI (1/16) W. Martz & Maltbie
3200' Arb. test to be comm.
by 12/1/64

NOTE: Show Sketch of Lease and Well Location in Above Space

Acreage contributed by:

Wm. C. Morris, Jr.

Ft. from N. Line Nadel & Gussner Ft. from S. Line

Ft. from W. Line

Ft. from E. Line

Date	Depth	
11/24/64		M.I.R.T. - Spud (6:30 p.m.)
11/25	205	Drlg. on surface hole (pyrite on #2 bit)
		8-5/8" @ 256' w/135 sx. cem., 3 gel., 3 c.c., P.D. @ 1:00 p.m. 11/25/64
11/27	1480	Drlg. (sho gas @ 1418')
11/28	1910	Drlg.
	2205	Grandhaven (-492)

Date	Depth	694726
11/30	2564	Trip
	2552	Topeka (-839)
DST #1	- 2208-2252	- Op 1 hr., wk. bl., Rec. (Tarkio) 90' o&GCM, BHP 779=93#, FP 39-47#
12/1	2775	Drlg.
12/2	2788	Heebner (-1075)
	2863	Lansing (-1150)
		(12' higher than Billie Morris 7' lower than Nadel & Gussman 2881-86' - 5' break
DST #2	- 2881-90'	- Op 80", Rec. 120' gas, 30' o&GCM, BHP (30") 811-116#, FP 31-39#, Temp. 96°
		(Rig down 24 hrs.)
12/3	2932	Drlg.
DST #3	- 3050-65'	- Op 2 hrs., wk. bl. TO REc. 90' wtry mud, BHP 967-889#, FP 31-47#, BHT 97°
12/5	3200	Drlg.
	3172	Conglomerate (-1459)
	3260	R.T.D.
		D & A 12/6/64