

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY

500 East Murdock,

Wichita, Kansas

11-14-31W

Company- D. R. LAUCK OIL CO., INC.
 Farm- Sharp No. 1

SEC. 11 T. 14 R. 31W
 NW NW NW

Total Depth. 4667

Comm. 6-26-52

Comp. 7-14-52


Shot & Tested.

Casing.

Isued. 7-26-52

County Gove

KANSAS



CASING:

8" 185' com. w/125 sx.

Elevation. 2851 D.F.

Production.

2853 (2nd).
Dry

Figures indicate Bottom of Formations.

All meas. from K.B.

shale & shells	1145
sand & shale	1215
shale & shells	1715
anhyd.	1790
shale red & shells	1856
anhyd.	1895
shale red & shells	2325
lime	2345
shale & lime	2835
shale & shells	2993
lime & shale	3340
lime brkn	3390
lime	3 575
shale & lime	3727
lime	3880
Hoebner shale	3284
lime & shale	3900
lime	4667
Total Depth	

Tops:

Hoebner shale	3880
Lansing	3923
Base K.C.	4261
Warmaton	4280
Cherokee	4397
Pre Des Moines	4482
Mississippi (St. Louis)	4562

~O. 4495-4502

D.O.T. 4491-4530 open 1 hr. rec. 63' mud,
few spots of oil. 520 $\frac{1}{2}$ BHP 15 min.

Zones of por. in Miss.

4580- 4604

4631-4637

4640-4646

no shows