

34 - 14 - 32W

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


Company- CONTINENTAL OIL CO.
Farm- R. B. Christy No. 1

SEC. 34 T. 14 R. 32W
SW SW SW

Total Depth. 4980
Comm. 12-8-54 Comp. 12-27-54
Shot or Treated.
Contractor. Graham-Messman-Rinehart
Issued. 1-22-55

County Logan

KANSAS



Elevation. 2668 KB

Production. dry

CASING:

13 3/8" 159' cem. w/175 sx

Figures Indicate Bottom of Formations.

sand & shale	114
shale	342
shale & shells	700
sand & shale	850
shale & shells	1464
shale	1501
shale & lime	3609
lime	3776
lime & shale	3846
lime	3993
lime & shale	4093
lime	4193
lime & shale	4257
lime	4322
sand & lime	4374
lime	4736
lime chert & sand	4753
lime chert, chalky lime	4780
lime	4913
Viola & Arbuckle	4950 RTD
Arbuckle	4980
Total depth	

Schlumberger Tops:

Heebner	3617
Toronto	3636
Lansing	3658
Base K. C.	4006
Miss.	4348
Viola?	4860
Arbuckle	4900

Sample Tops:

Heebner	3619
Toronto	3636
Lansing	3658
Mississippi	4346
Arbuckle	4900