

TKT #61

Sholom Drilling Inc.

BOX 7027 - TULSA, OKLAHOMA

TESTING DIVISION

Date 11-16-62Charge to Kaiser-Francis-Pet Operating Co Owner of Well SameMailing Address 905 Palace Bld. Contractor Sholom Drg. Co. Inc.City and State Tulsa 3, Oklahoma Rig No. 1Lease Herl Well No. A-2 County Ellis State KansD. S. T. No. 1 No. Charts _____ Sec. 35 Twp. 14 Rg. 19

TOTAL DEPTH	<u>3563</u>	INITIAL CLOSED IN TIME	<u>20</u> MIN.
HOLE SIZE	<u>7 7/8</u>	TOOL OPEN FLOW PERIOD	<u>60</u> MIN.
RATHOLE SIZE	<u>—</u>	FINAL CLOSED IN TIME	<u>30</u> MIN.
TOP PACKER DEPTH	<u>3518</u>	INITIAL HYDRO MUD PRESSURE	<u>2020</u> LBS.
BOTTOM PACKER DEPTH	<u>3524</u>	INITIAL CLOSED IN PRESSURE	<u>480</u> LBS.
SIZE PACKER	<u>6 3/4</u>	INITIAL FLOW PRESSURE	<u>0</u> LBS.
LENGTH ANCHOR	<u>39'</u>	FINAL FLOW PRESSURE	<u>0</u> LBS.
MUD WEIGHT	<u>10.1</u>	FINAL CLOSED IN PRESSURE	<u>0</u> LBS.
VISCOSITY	<u>40</u>	FINAL HYDRO MUD PRESSURE	<u>2020</u> LBS.

REMARKS:

Weak blow for 20 mins. Flush tool VERY
Weak for 15 mins.

Rec. 25' mud with few specks of oil

BASE PRICE \$ _____
 EXTRA EQUIP. \$ _____
 OTHER \$ _____
 TOTAL \$ _____

The above job was done, and all tools were used under the exclusive control, direction and supervision of the owner, operator or his agent whose signature appears below. Sholom Drilling Inc., shall not be liable for damage of any kind to the property or the personnel of the one for whom a test is made or for any loss suffered or sustained, directly or indirectly, through the use of its equipment, or its statement or opinion concerning the result of any test. Tools lost or damaged in the hole shall be paid for at cost by the party for whom the test is made.

Test Operator: Norman Rodie Test Approved By: Horton Cox

TKT #62

Sholom Drilling Inc.

BOX 7027 - TULSA, OKLAHOMA

TESTING DIVISION

Date 11-18-62

Charge to Kaiser-Francis Petroleum Corp. Owner of Well Same
 Mailing Address 905 Palace Bldg. Contractor Sholom Drilling Co. Inc.
 City and State Tulsa, Oklahoma Rig No. 1
 Lease Hertl Well No. A-2 County Ellis State Kansas
 D. S. T. No. 2 No. Charts _____ Sec. 35 Twp. 14 Rg. 19

TOTAL DEPTH	3750	INITIAL CLOSED IN TIME	20 MIN.
HOLE SIZE	7 7/8	TOOL OPEN FLOW PERIOD	60 MIN.
RATHOLE SIZE	—	FINAL CLOSED IN TIME	30 MIN.
TOP PACKER DEPTH	3737	INITIAL HYDRO MUD PRESSURE	2120 LBS.
BOTTOM PACKER DEPTH	3743	INITIAL CLOSED IN PRESSURE	1150 LBS.
SIZE PACKER	6 3/4	INITIAL FLOW PRESSURE	410 LBS.
LENGTH ANCHOR	7'	FINAL FLOW PRESSURE	1010 LBS.
MUD WEIGHT	10.2	FINAL CLOSED IN PRESSURE	1150 LBS.
VISCOSITY	43	FINAL HYDRO MUD PRESSURE	2120 LBS.

REMARKS:

Strong blow Through out Test
Rec. 2230 Water

BASE PRICE \$ _____
 EXTRA EQUIP. \$ _____
 OTHER \$ _____
 \$ _____
 TOTAL \$ _____

The above job was done, and all tools were used under the exclusive control, direction and supervision of the owner, operator or his agent whose signature appears below. Sholom Drilling Inc., shall not be liable for damage of any kind to the property or the personnel of the one for whom a test is made or for any loss suffered or sustained, directly or indirectly, through the use of its equipment, or its statement or opinion concerning the result of any test. Tools lost or damaged in the hole shall be paid for at cost by the party for whom the test is made.

Test Operator: Leonard WilliamsonTest Approved By: Stanley Cox