

2-14-39w ✓


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- D.R. LAUCK OIL CO., INC.
Farm- Jennings No. 1

SEC. 2 T. 14 R. 39W
 C NE NE

Total Depth. 4868'
Comm. 9-1-65 Comp. 9-15-65
Shot or Treated.
Contractor. Co. Tools.
Issued. 1-1-66

County Wallace
 KANSAS



CASING:

Elevation. 3366 D.F.

8 5/8" 209' w/165 sx cem.

Production. DRY

Figures Indicate Bottom of Formations.

shale	830
chalky lime	905
shale, shells	1205
sand, shale	1270
shale, shells	1660
shale, lime strks	2085
red bed, shells	2347
Anhydrite, red bed	2540
red bed	2575
Anhydrite	2605
lime, shale	3615
lime	3710
shale, lime	3790
lime	3911
Heebner	3913
lime	4140
lime, cherty	4175
lime	4218
lime(Dense), some	
cherty	4260
lime	4478
lime, shale	4511
lime	4700
lime, sand	4725
lime	4868
Rotary Total Depth	

TOPS:	SAMPLES WELEX	
Blaine		1990
Cimarron Anhydrite		2560
Topeka	3764	3760
Heebner	3911	3909
Toronto	3931	3931
Lansing	3962	3959
B/Kansas City	4345	4343
Marmaton	4363	4364
Cherokee	4491	4490
Morrow shale	4676	4673
Morrow sand	4710	4712
Mississippian	4791	4789
Cte. Genevieve	4791	4789

DST-None.