

9-14-42W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas

Company- COOPERATIVE REFG. ASSN.  
Farm- Goodrich "B" No. 1

SEC. 9 T. 14 R. 42W  
C NW SE

Total Depth. 5427'  
Comm. 5-4-60 Comp. 5-31-60  
Shot or Treated.  
Contractor. Honaker Davis Drlg. Co.  
Issued. 7-16-60

County Wallace  
KANSAS



Elevation. 3856' DF

Production. DRY

CASING:

8 5/8" 441' w/200 sx cem.

Figures Indicate Bottom of Formations.

clay, sand	470
shale, sand stks	990
shale	1552
shale w/iron stks	1660
shale w/sand stks	1755
shale, iron	1945
shale, shells	2200
shale, red bed	2350
red bed	2715
red bed, shale	2854
anhydrite	2888
shale, red bed	3205
red bed, lime	3420
shale w/lime stks	3490
shale, red bed	3544
lime	3675
lime, shale	4268
lime	4695
chert, lime	4746
shale, lime	4774
lime	4818
lime, shale	5172
lime	5397
lime, chert	5427
Rotary TotalDepth	

TOPS: SCOUT

Anhydrite	2854
Council Grove	3338
Topeka	3966
Heebner	4150
Toronto	4182
Lansing	4210
Marmaton	4594
Cherokee	4793
Morrow	5002
Morrow sand	5011
Mississippi	5084