

State

Kansas

County

Ellsworth

Company Messman-Rinehart Oil Co.

Well No. 1890

Farm

Foran

Survey

Block No.

Sec. 5

Twp. 14 S


Range 9 W

Co-Ord.

Elev. 1708' D/F
1710' K/B

Ctr. SW/4

M-R Rig



50% - A. A. Seeligson, Jr. et al
25% - Chicago Group
25% - M-R Oil Co.

ORI - J. George Klein

2600' Bs Tarkio test

NOTE: Show Sketch of Lease and Well Location in Above Space

Ft. from N. Line

Ft. from S. Line

Ft. from W. Line

Ft. from E. Line

Date	Depth	
4/28/60		Spud - 8-5/8" @ 277' w/150 sx cem., 4' gel., 3 c.c., P.D. @ 9:00 p.m. 4/28/60
4/30		SUS - 7:00 a.m.
	1270	Herington (#2 @ 1275) (#3 @ 1615)
5/1	1490	Drlg.
5/2	1800	Drlg.
5/3	1326	Winfield (#384)
	2120	Coming out for D.S.T.

Date	Depth	
5/4	1330	Fishing (spotted w/20 B0 & pulled loose)
	1391	Ft. Riley (#319)
	2162	Tarkio Lm (-452)
5/5	D.S.T. #1	- 2080-2120 - Op 1½ hrs., GTS in 1' 27" (will burn-tstm) Rec. 80' gas-cut mud, 80' gas-cut salt wtr. & lgt. BS BHP 720-500#, FP 20-150#
5/6	D.S.T. #2	- 2136-2230 - Op 1 hr., Rec. 10' mud, BHP 860-590#, FP 400-40#
	2230	R.T.D. (waiting on orders) 4½" @ 1548' w/125 sx. cem., 2 gel,
5/16		M.I.C.T. - Perf. lower zone 300' gas - 1398-1406' w/24 ^s (E gun) no sho, Treated w/200 gal. M.C.A., ft. sho gas, 1½ BW/2hrs. Perf. 1309-11 w/4 ^s , no sho Perf. 1416-20 w/8 ^s , no sho Perf. 1452-56 w/6 ^s , no sho Perf. 1334-38' w/6 ^s , no sho

128069

State Kansas County Ellsworth


Company Messman-Rinehart Oil Co. Well No. 1

Farm Foran

Survey _____

Block No. _____ Sec. 5 Twp. 14S Range 9 W

Co-Ord. _____ Elev. 1710 K/B



Page 2

NOTE: Show Sketch of Lease and Well Location in Above Space

Ft. from N. Line

Ft. from S. Line

Ft. from W. Line

Ft. from E. Line

Date	Depth	
		Set L-W Plug @ 1320'
		Perf. 1282-94' w/22 ^s
		Treated w/500 gal. MA.-fr.sho gas
		1000 gal. 15% acid,
5/19		Swb. back 34,000 cfg.,
		Swbg. 150,000 cfg
		To set awxhile & blow well
		D & A