

C.H.FROST & FRANK E.MCMILLIN JR.
Dolechek No. 1.

SEC. 36 T. 14 R. 8W
Gen NE SW

Total Depth. 3515'


Comm. 1-6-37 Comp. 6-2-37

Shot or Treated.

Contractor.

Issued. 9-25-37

County. Ellsworth



CASING:

15 1/2" 170'
12 1/2" 354'
8 1/4" 2756'
6 5/8" 3020'
5 3/16" 3348'

Elevation.

Production. Dry

Figures Indicate Bottom of Formations.

cellar	8	shale blue	1985	shale	3308
sand	25	lime	1990	shale greenish	3340
shale blue	65	shale blue	2045	shale blue	3348
shale lgt	95	shells & shale	2060	lime	3351
red rock	105	shale blue	2110	shale blue	3376
shale lgt	120	lime	2130	Viola lime	3455
shale red	150	shale & shells	2180	shale green	3470
sand	170	lime	2185	lime	3490
shale white	195	shale blue	2207	shale drk	3505
sand	215	lime	2210	pyrites iron	3507
shale blue	225	shale blue	2215	Siliceous lime HFW	3515
shale brown	250	lime	2223	Total Depth.	
shale blue	265	shale	2250		
sand	270	lime	2260		
shale blue	375	shells & shale	2290		
red rock	550	shale blue	2295		
shale blue	570	lime hrd	2323		
anhydrite & shale	590	shale blue	2350		
shale brown	620	lime	2400		
red rock	660	shale blue	2405		
shale blue	780	lime 1 blr wat	2465		
salt	1012	shale	2470		
shale blue	1022	sdv lime	2585		
shale blue	1035	sdv lime HFW	2595		
lime	1055	lime	2605		
shale blue	1080	shale blue	2625		
lime	1095	lime HFW	2647		
shale	1105	shale red	2651		
lime	1120	shells & shale	2671		
shale	1135	sdv limo wtr	2688		
lime	1155	shale blue	2693		
shale red	1170	lime	2710		
shale blue	1182	shale	2715		
lime	1200	lime	2720		
shale blue	1215	shale	2745		
lime	1260	lime	2770		
shale brown	1280	lime	2775		
lime 1/4 BW Hr.	1315	shale	2780		
shale & lime shell	1335	lime	2835		
lime	1385	sdv lime	2865		
sdv lime	1415	lime	2900		
shale brown	1425	shale	2915		
lime	1440	lime	3015		
shale blue	1475	shale blue	3020		
lime	1565	lime	3076		
shale brown	1600	bluish red shale	3085		
shale blue	1608	shells & shale	3105		
lime	1650	shale brown	3118		
shale brown	1665	lime	3124		
lime	1720	shale brown	3130		
lime shells & shale	1775	lime	3150		
lime	1800	shells & shale	3170		
shale & limo	1854	lime 6 blr wat	3190		
shale blue	1875	sdv lime	3201		
limo shells & shale	1935	red rock	3206		
shale red	1955	sdv lime	3237		