

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
Union National Bank Bldg, Wichita, Kansas

P.H. JOSEPH.
Kasper No. 2


SEC 6 T. 14 R. 9W.
C NW NE

Total Depth. 1400 P.B. 1396
Comm. 11-10-35 Comp. 12-4-35
Shot or Treasured.
Contractor.
Issued. 12-21-35.

County. Ellsworth.

CASING.

10" 40' 53/16" 1376'
8 1/4" 358'10"
65/8" 481'



Elevation.

Production. 750,000 Gas.

Figures Indicate Bottom of Formations.

surface soil	4	lime	1130
clay yellow	28	shale blue	1160
water sand	36	broken lime	1176
clay yellow	48	shale light and lime shells	1200
shale blue	53	shale blue and lime shells	1263
shale blk	75	lime	1276
shale light	115	Gas at 1260 approx.	
10 BWPHR at 100 to 115		shale blue	1315
red rock	120	sdv shale white	1326
shale light	125	lime	1346
shale blue	130	shale blue	1364
Gumbo	135	red rock	1376
shale light	148	shale blue	1377
red rock	170	lime	1400
Gumbo	185	Total Depth.	
red rock	206	Plugged back to 1396	
lime	210	Gas from 1382-1396	
red rock	235		
shale grey	250		
lime	255		
shale light	345		
sand HFW	355		
shale blue	360		
shale light	385		
sand white	395		
probably water.			
shale light & lime shells	415		
lime and iron	416		
Gumbo blk	440		
shale grey	460		
shale brown	480		
shale blue	490		
shale brown	525		
red rock	675		
shale blue	735		
shale brown	785		
shale blue	790		
shale brown	815		
shale blue	902		
salt	1100		
lime	1103		
shale blue	1119		