

KANSAS

IMPORTANT
Kans. Geo. Survey request
samples on this well.

SEP 8 0 1980

WELL COMPLETION REPORT AND DRILLER'S LOG

S. 33 T. 14S R. 9 ^{XX} W

Loc. NW NE NW

County Ellsworth

API No. 15 _____
County _____ Number _____

Operator
Rains & Williamson Oil Co., Inc.

State Geological Survey
WICHITA BRANCH

Address
435 Page Court, 220 W. Douglas


Well No. #2 Lease Name Adamek

Footage Location
feet from (N) (S) line _____ feet from (E) (W) line _____

Principal Contractor Rains & Williamson Oil Co., Inc. Geologist Stephen Kreidler

Spud Date 7-26-80 Date Completed 8-2-80 Total Depth 3055' P.B.T.D. _____

Directional Deviation _____ Oil and/or Gas Purchaser _____



Locate well correctly
Elev.: Gr. 1654

DF _____ KB 1659

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
	12 1/4"	8 5/8"	20#	522'	Common 60/40 poz.	150 sx. 150 sx.	2% gel, 3% cc. 2% gel, 3% cc.
		4 1/2"	9 1/2#	3048'	60/40 poz.	125 sx.	10% salt, 3/4 of 1% CFR2, 10% SW flush.

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

Size	Setting depth	Packer set at

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated

INITIAL PRODUCTION

Date of first production _____		Producing method (flowing, pumping, gas lift, etc.) _____			
RATE OF PRODUCTION PER 24 HOURS	Oil _____ bbls.	Gas _____ MCF	Water _____ bbls.	Gas-oil ratio _____ CFPB	
Disposition of gas (vented, used on lease or sold) _____			Producing interval (s) _____		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 245 No. Water, Wichita, Kansas 67202. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator Rains & Williamson Oil Co., Inc.

DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:
Oil

Well No. #2

Lease Name Adamek

S 33 T 14 S R 9 ^{XX}_W

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
DST #1 - 2809-2837, 30 (30) 60 (60). Rec. 40' O&GCM, 370' Heavy Frothy Gassy Oil, 180' Gassy Oil, 60' O&GCW. FP's 293-246, 316-422. IBHP 983, FBHP 995. Temp. 108 ^o .			<u>E. LOG TOPS</u>	
			Howard	2308 (-649)
			Topeka	2352 (-693)
			Heebner	2609 (-950)
			Toronto	2629 (-970)
			Douglas	2643 (-984)
			Brown Lime	2713 (-1054)
			Lansing	2739 (-1080)
		BKC	3030 (-1371)	
		LTD	3049 (-1390)	

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received

Wilson Rains
 Wilson Rains
 Signature
 President
 Title
 8-21-80
 Date