

MILLER TESTING COMPANY

Box 547

GREAT BEND, KANSAS

Company THUNDERBIRD DRILLING, INC.

Lease and Well No. STEELE ESTATE B #1

County LOGAN

State KANSAS

Date 10-29-79

Formation Test No. 1 Total Depth 3965 Elev. _____
Interval Tested 3925 To 3965 Anchor Length 40'
Size Hole 7 7/8 Size Drill Pipe 4 1/2 X. Size Packer 6 3/4
Mud Weight 9.4 Viscosity 40 Water Loss 13.2 c.c. Bottom Hole Temp. 108 °F
Chokes: Top 1/2 Bottom 1/2 Ticket No. 18199
Length of Drill Collar _____ I. D. _____ Length Flexweight 868' I. D. 2.76

RECOVERY

FIRST OPENING: FAIR TO GOOD BLOW THROUGHOUT OPENING.
SECOND OPENING: GOOD BLOW.

1350 FEET OF WATER.


Lease and Well No. _____

STEELE ESTATE B #1

9-14S-32W

Formation Test No. _____

1



Tool Open: 1st Flow hr. 45 mins: Shut-in Initial hr. 45 min: 2nd Flow hr. 45 min: Shut-in Final hr. 45 min.

	Field Reading	Corrected Reading
(A) Initial Hydrostatic Pressure	<u>1994</u>	<u>2002</u>
(B) Initial 1st Flow Pressure	<u>51</u>	<u>70</u>
(C) Final 1st Flow Pressure	<u>421</u>	<u>419</u>
(D) Initial Shut-in Pressure	<u>1299</u>	<u>1310</u>
(E) Initial 2nd Flow Pressure	<u>421</u>	<u>419</u>
(F) Final 2nd Flow Pressure	<u>622</u>	<u>612</u>
(G) Final Shut-in Pressure	<u>1299</u>	<u>1303</u>
(H) Final Hydrostatic Pressure	<u>1994</u>	<u>2002</u>

18199