


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company • A.R.JONES-E.T.LINDSAY-R.S.DUFFIELD
Farm • Robson No. 1.

SEC. 12 T. 15 R. 1 W
CEL NE NE
330' FEL 660' FNL NE $\frac{1}{2}$

Total Depth. 2658' Hall. Meas.
Comm. 11-8-43 Comp. 12-12-43
Shot or Treated.
Contractor. Saco Oil Co.
Issued. 2-5-44

County. Saline
KANSAS



CASING:
20" 22'6" R&P 10" 1990' R&P
15 $\frac{1}{2}$ " 420' R&P 8 $\frac{1}{4}$ " 2336' R&P
12 $\frac{1}{2}$ " 1386' R&P 7" 2620' UR 2650' HSIM Cem. Elevation. _____
Production. Dry
Figures Indicate Bottom of Formations.

clay yellow	35	lime	910	lime	2040
shale blue	118	slate & shells	960	shale	2043
lime	130	shale	980	lime brkn	2077
shale	135	slate & shells	1050	shale	2090
shale & shells	160	red rock	1055	lime	2100
lime	170	shale	1060	sand	2125
shale	180	red rock	1070	lime	2155
lime	185	shale	1085	shale	2172
shale	210	red rock	1100	hole caving 2110-2249	
lime	225	shale	1160	lime	2249
slate & shells	240	lime shells	1175	shale blk	2252
red rock	245	lime hd	1190	lime	2317
lime	250	shale & shells	1245	shale dk	2320
lime & red rock	265	shale	1250	shale blue	2330
shale	270	lime	1257	shale	2334
lime	285	shale	1265	lime	2347
shale	300	lime shells	1290	shale	2351
red rock	310	Meas. Corr. 1312		lime	2354
lime	335	red rock	1320	shale-cvg	2359
shale	355	lime	1325	lime	2366
lime	360	shale	1384	shale	2395
red rock	380	lime brkn	1395	lime	2400
red rock & lime	420	shale	1445	shale lgt	2420
shale	425	lime-caving	1450	lime	2425
lime	500	lime	1452	shale	2450
lime sdy	515	shale	1455	lime	2463
shale	520	lime	1460	shale dk	2478
red rock	525	shale	1485	shale & shells	2500
lime	535	shale sdy	1495	lime shells	2515
slate & shale	550	shale	1520	slate & shells	2525
lime brkn	565	lime	1525	lime	2530
shale	575	lime brkn	1535	shale	2540
lime	585	lime	1550	slate & shells-cvg	2565
shale	590	lime brkn	1560	shale	2590
lime	615	lime	1570	lime	2592
shale	630	shale	1605	shale	2618
lime	637	lime	1630	lime	2621
shale & shells	655	shale	1635	lime lgt	2631
lime	665	lime	1640	lime	2650
shale	690	shale	1665	T.D. Cable Meas.	
lime	695	lime	1675	T.D. Hallib. Meas. 2658	
shale	700	shale	1680	Total Depth.	
lime brkn	715	lime	1685		
shale	725	shale	1690	LBWPH 290-800; LBWPH 1485-95	
lime	735	lime	1805	2BWPH 2040-65; HW 2110-25	
shale	740	lime shells-cvg	1845	HW 2640-50	
lime	750	shale	1853		
shale & shells	760	red rock-cvg	1870	Oil Shows:	
shale	782	shale	1932	2620 - 2 $\frac{3}{4}$ BO after standing 30	
red rock	785	lime	1935	min. in 35'7" tube	
lime sdy	805	shale	1940	2621 - Hole filled 275'w/wtr in	
shale	810	lime	1945	3 hrs	
lime	815	red rock	1950	2631 - 3 BWPH & 1 BOPH bailing	
shale	835	shale	1960	& testing	
shale	850	shale sdy 1990-Top KC			
lime	875	lime	2005		
shale	885	slate & shells	2015		

T.D.
2658
34 days